



DoD Executive Agent

Office of the
Assistant Secretary
of the Army
(Installations and
Environment)

Implementing Distributed Wind Power at Military Installations: Site Assessment, Approval and System Design

Heidi Anne Kaltenhauser,
NDCEE/CTC

The NDCEE is operated by:  *Concurrent Technologies Corporation*

Technology Transition – Supporting DoD Readiness, Sustainability, and the Warfighter

Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE JUN 2010		2. REPORT TYPE		3. DATES COVERED 00-00-2010 to 00-00-2010	
4. TITLE AND SUBTITLE Implementing Distributed Wind Power at Military Installations: Site Assessment, Approval and System Design				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) National Defense Center for Energy and Environment (NDCEE), Concurrent Technologies Corporation, 100 CTC Drive, Johnstown, PA, 15904				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution unlimited					
13. SUPPLEMENTARY NOTES Presented at the NDIA Environment, Energy Security & Sustainability (E2S2) Symposium & Exhibition held 14-17 June 2010 in Denver, CO. U.S. Government or Federal Rights License					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT Same as Report (SAR)	18. NUMBER OF PAGES 25	19a. NAME OF RESPONSIBLE PERSON
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified			

Presentation Highlights

- Task Overview
- Site Assessment
- Site Approval
- Initial System Design/Procurement
 - SOW
 - RFP
 - Equipment Evaluation
 - Procurement
- Final System Design
- Next Steps

FY07 Regional Sustainability Solutions Technology Development, Demonstration, and Validation – Pacific Rim Region

Identify and conduct a technology demonstration/validation project in the Hawaiian Island region to support the Service's sustainability goals and objectives

Team Members

- Naval Facilities Engineering Command, Hawaii (NAVFAC Hawaii)
- Pearl Harbor Naval Complex (Pearl City Peninsula Family Housing)
- Ohana Military Communities/Forest City Military Communities (FCMC) Hawaii
- National Renewable Energy Laboratory (NREL)
- National Defense Center for Energy and Environment (NDCEE)

Project Approach

- Identify key sustainability issues for Hawaii
- Identify/evaluate technology opportunities that will address the issues
- Demonstrate a technology opportunity that has transition potential
 - Site Assessment/Approval
 - Equipment Specifications/Evaluation
 - Procurement and Installation
 - Demonstration and Final Report
- Technology transition with focus on Pacific Rim Region

Initial Work

- Identification of key regional issues resulted in a decision to demonstrate a renewable energy system
 - Helps meet numerous local and military initiatives
 - Reduces the military's utility costs
 - Eases energy security concerns
 - Helps protect Hawaii's unique cultural and natural resources by reducing fossil-fuel generated pollution
- Technical assessment of six technologies indicated that solar and wind were the best choices
- Initial economic evaluation of wind/solar indicated that wind had fastest investment recovery/lowest financial risk

Pre-Procurement Activities

1. Preliminary Site Assessment
2. Site Approval
3. Site Assessment
4. Equipment Specifications
5. Request for Proposal
6. Equipment Evaluation

Site Assessment

Preliminary Site Assessment

- Conducted by NREL
- Wind maps
- Site visit
- Decision to proceed

Site Assessment

- Anemometer tower at site
- 6 months of wind data




Wind Resource

Site Assessment


- Anemometer data
 - Data collection period: July 17, 2009 – February 8, 2010
 - Data collection: 10-minute intervals at various heights
 - 50 meters West
 - 50 m East
 - 35 m West
 - 35 m East
 - 20 m West
 - 20 m East
 - Data summary report provided by NREL

Pearl City Wind Rose at 35m East (W/m²)


Data Collected July-Feb



Pearl City Wind Speed Distribution by month at 35m East



Pearl City Turbulence Intensity at 35m East




Site Approval Process

- Requirements
 - NEPA CATEX
 - State Historic Preservation Officer (SHPO) approval needed as it is an historic site
 - Navy approval
- Responsibility
 - Bulk of work conducted by Ohana
 - NDCEE provided technical input to process

CATEX

- Effect on public health and safety
- Effect on wetlands, threatened or endangered species, historic or archeological resources, or hazardous waste sites
 - Sampling and disposal plan due to PCBs

SHPO Requirement – View from Historic Site



Navy Approval – Requested Info

- Pole type of wind turbine (tube or lattice)
- Foundation type/dimensions
- Overall height
- Rotor diameter
- Projections
- Electric connections
- Ownership
- Site description
- Decibel level
- Previous restoration information

Development of Equipment Specifications

- Met with Navy to discuss interconnectivity issues and data monitoring communication requirements
- Navy provided additional requirements and design guide
- 40 kW – 100 kW turbine
- Turnkey activities
- Client capabilities
- Budget/schedule/site constraints

Vendor SOW Requirements

- Task 1: Investigation
- Task 2: Construction Design
- Task 3: Implementation
- Task 4: Equipment Commissioning and Testing
- Task 5: Distribution of Technical Manuals & Publications
- Task 6: Demonstration
- Task 7: Sustainment
- Task 8: Documentation


RFP

- Issued November 2009
- Requested a turnkey system
- Provided:
 - Wind resource data summary
 - Aerial photo of proposed turbine location
 - Utility lines in immediate area
 - NAVFAC utility requirements
 - HECO Utility Interconnection Agreement
 - Initial geotech results
- Identified 6 vendors
- Held a vendor teleconference
- Addressed email questions
- Received 3 proposals
- Conducted technical and economic evaluation

Equipment/Proposal Evaluation

- Technical Evaluative Criteria
 - #1: *Meets all Statement of Work Requirements*
 - #2: *Experience and History*
 - #3: *Equipment*
 - #4: *Schedule*
- Economic Evaluative Criteria
 - #1: *Total Costs*
 - #2: *Capital Investment Financial Indicators*
 - #3: *Confidence in Proposal Price*

Power Curve Comparison



Economic Evaluation

- Small Wind Energy Economic Tool (version 2.0) developed by NREL
- Uses average wind speed and distribution taken from measured data
- Results are not precise but rather provide a rough estimate result.
- Sufficient to conduct a comparison between the different turbines
- Result highly dependent on accuracy of power curve
 - Third-party validated
 - Estimated wind curve

Turbine Site



Summary/Lessons Learned

- Conducted thorough site assessment with assistance from NREL and Ohana
- Military site approval process is quite lengthy
- Owner/Utility requirements must be identified
- Limited turnkey vendor options
- Turbine availability is an issue
- Accuracy of power curve is critical
- A multi-organizational team is beneficial to completing project

Next Steps

- Work with Ohana and vendor on system design
- Install wind turbine system and auxiliary equipment
- Execute start-up and commissioning activities
- Demonstrate/validate technology
- Transition Technology



DoD Executive Agent

Office of the
Assistant Secretary
of the Army
(Installations and
Environment)

www.ndcee.ctc.com

Points of Contact

Heidi Anne Kaltenhauser
NDCEE/CTC
kaltenha@ctc.com
(502) 425-1385

NDCEE Program Management Office
(703) 602-5500

This work was funded through the Office of the Assistant Secretary of the Army (Installations and Environment) and conducted under contract W74V8H-04-D-0005 Tasks 440/501. The views, opinions, and/or findings contained in this paper are those of the author and should not be construed as an official Department of the Army position, policy, or decision unless so designated by other official documentation.